

IF IN DOUBT - PLEASE ASK

PRIOR TO THE COMMENCEMENT OF WORK CHECK SERVICES PLANS AND THOROUGHLY SCAN THE WORKING AREA WITH A CAT AND GENNY

MOBILE HOMES TO BE SITED IN STRICT ACCORDANCE WITH THE MODEL STANDARDS 1989

DIMENSIONS INDICATED RELATE TO ADD 30mm EACH FACE FOR BASE ADD 75mm TO EACH FACE IN THE CASE OF A GARAGE RAFT DEDUCT 25mm FROM EACH FACE IN THE CASE OF A PIP FOUNDATION

MANUFACTURED MOBILE HOMES IMPERIAL DIMENSIONS ARE FOR CONCRETE ONLY

STUCCO FINISH OF THE MOBILE HOME WALLS IN THE CASE OF A MOBILE HOME WITH A GARAGE RAFT DEDUCT 25mm FROM FOUNDATION

DO NOT EXCEED THE METRIC SIZES SHOWN ON CONCRETE ONLY

CONCRETE BASE TO BE LAID LEVEL AND SQUARE AND IN ACCORDANCE WITH STANDARD DETAILS, CONSTRUCTION NOTES (CURRENT REVISIONS) AND SAFE WORKING PRACTICE REPORTS. ANY UNTOWARD ON SITE CONDITIONS TO BE REPORTED TO HEAD OFFICE IMMEDIATELY

CONCRETE BASE TO BE LAID LEVEL AND SQUARE AND IN ACCORDANCE WITH STANDARD DETAILS, CONSTRUCTION NOTES (CURRENT REVISIONS) AND SAFE WORKING PRACTICE REPORTS. ANY UNTOWARD ON SITE CONDITIONS TO BE REPORTED TO HEAD OFFICE IMMEDIATELY

SHED POSITIONS SHOWN ARE FOR INDICATION PURPOSES ONLY. SHEDS CAN BE MOVED TO SUIT MOBILE HOMES SELECTED



Site Area = 5.642 hectares
Useable Area = 4.179 hectares

Existing Homes - 139no
(102 Twins 37 Singles)

Homes Not Yet Sited - 28no
(14 Twins 14 Singles)

187 TOTAL